

INSPECTIONS

- Footer inspection with reinforcement installed as well as bulkheads if required, (rebar must be elevated 3" off bottom of footer).
- Underfloor plumbing before pouring concrete floor.
- Foundation inspection (4" Leach bed pipe covered with gravel and silt paper) prior to backfilling, (Stone must be at least 6" above pipe and 12" out from edge of footings).
- Plumbing rough in.
- Rough in mechanical.
- Electrical rough in.
- Framing inspection (only done after all plumbing, mechanical and electrical rough ins).
- Insulation inspection.
- Mechanical final.
- Electrical final.

Building and plumbing final.