

Rockingham County
Erosion and Sediment Control
Unit Prices For Determining Bond Fees
Effective 02/15/2019

<u>Minimum Standard #</u>	<u>SEDIMENT DEVICE</u>	<u>COST *</u>	<u>UNIT</u>
3.01	\$0.00 Safety Fence	\$4.00	Linear Foot
3.02	\$0.00 Construction Entrance	\$1,500.00	Each
3.05	\$0.00 Silt Fence	\$3.00	Linear Foot
3.07	\$0.00 Curb Inlet Protection	\$200.00	Each
3.08	\$0.00 Culvert Inlet Protection	\$250.00	Each
3.09	\$0.00 Diversion Berm	\$3.00	Linear Foot
3.10	\$0.00 Fill Diversion	\$2.00	Linear Foot
3.12	\$0.00 Diversion	\$9.00	Linear Foot
3.13	\$0.00 Sediment Trap - 1 acre	\$2,250.00	Each
	\$0.00 Sediment Trap - 2 acres	\$2,500.00	Each
	\$0.00 Sediment Trap - 3 acres	\$3,000.00	Each
3.14	Sediment/Stormwater Basin (Lump Sum*)		
3.16	\$0.00 Paved Flume	\$60.00	Square Yard
3.17	\$0.00 Stormwater Conveyance Channel		
	\$0.00 Seeded	\$6.00	Square Yard
	\$0.00 Sodded	\$20.00	Square Yard
	\$0.00 Temporary Matting	\$20.00	Square Yard
	\$0.00 Permanent Matting	\$26.00	Square Yard
	\$0.00 Riprap	\$60.00	Square Yard
3.18	\$0.00 Outlet Protection		
	\$0.00 Riprap	\$60.00	Square Yard
	\$0.00 Grouted Riprap	\$50.00	Square Yard
	\$0.00 Concrete	\$40.00	Square Yard
3.20	\$0.00 Rock Check Dam	\$30.00	Square Yard
3.21	\$0.00 Level Spreader	\$12.00	Square Yard
3.22	\$0.00 Temporary Seeding/Mulch	\$2,500.00	Acre
3.23	\$0.00 Permanent Seeding/Mulch	\$3,000.00	Acre
	\$0.00 Bio-retention	\$18.00	Square Foot
	\$0.00 Underground Detention	\$10.00	Cubic Foot
	\$0.00 Wet Pond/ Extended Detention	\$6.00	Cubic Yard
Contingency	\$0.00 25 % of the total		
TOTAL	\$0.00		

*Note: Engineering firms shall provide an estimate on sediment and stormwater basins as well as any item not listed above.